


# ROADWAY RECONSTRUCTION PLANS


## POLLY PEABODY ROAD

### BEDFORD, NEW HAMPSHIRE




BEDFORD PUBLIC WORKS  
55 CONSTITUTION DRIVE  
BEDFORD, NH 03110

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
	<b>TITLE SHEET</b>
<b>1 - 4</b>	<b>PLAN AND PROFILES</b>
<b>5</b>	<b>DRAINAGE NOTES</b>
<b>6</b>	<b>TYPICAL SECTION</b>
<b>7</b>	<b>ROADWAY DETAILS</b>
<b>8 - 9</b>	<b>DRAINAGE DETAILS</b>
<b>10</b>	<b>EROSION CONTROL DETAILS</b>
<b>11</b>	<b>EROSION CONTROL NOTES</b>
<b>12 - 21</b>	<b>CROSS SECTIONS</b>



APRIL 6, 2022




PLAN SET NO. \_\_\_\_\_

























[illegible]











POLLY PEABODY ROAD RECONSTRUCTION PLANS  BEDFORD, NEW HAMPSHIRE	PREPARED FOR:  TOWN OF BEDFORD 55 CONSTITUTION DRIVE BEDFORD, NEW HAMPSHIRE 03110		DRAINAGE DETAILS 2			
SHEET: 9 OF 21	SCALE: AS SHOWN	DATE: APRIL 6, 2022		NO.	DATE	REVISION DESCRIPTION



1. FILTER FABRIC SILT FENCE MUST BE INSTALLED AT LEVEL GRADE. BOTH ENDS OF EACH FENCE SECTION MUST BE EXTENDED AT LEAST 8 FEET UPSLOPE AT 45 DEGREES TO THE MAIN FENCE ALIGNMENT.
2. SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH ONE-HALF (1/2) THE ABOVE GROUND HEIGHT OF THE FENCE.
3. ANY FENCE SECTION WHICH HAS BEEN UNDERMINED OR TOPPED MUST BE IMMEDIATELY REPLACED WITH A ROCK FILTER OUTLET.

## **FILTER FABRIC SILT FENCE**


NOT TO SCALE



NOT TO SCALE



NOT TO SCALE



## GRASS-LINED SWALE

NOT TO SCALE




NOT TO SCALE



NO STAPLES TO BE OVER 24"  
APART CENTER TO CENTER


## **MULCH NETTING INSTALLATION**

NOT TO SCALE



NOTE:

STABILIZED CONSTRUCTION ENTRANCE THICKNESS WILL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING NEW ROCK AND REMOVING "CLOGGED" ROCK AS NECESSARY. A STOCKPILE OF ROCK MATERIAL WILL BE STORED ON THE SITE FOR THIS PURPOSE. AT THE END OF EACH CONSTRUCTION DAY, ALL SEDIMENT DEPOSITED ON PUBLIC ROADWAYS WILL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE.



## **STABILIZED CONSTRUCTION ENTRANCE**

NOT TO SCALE

GENERAL NOTES:

1. SILT FENCE SHALL CONSIST OF AN APPROVED PREFABRICATED SILT FENCE WITH FABRIC ATTACHED TO POSTS AND SHALL BE ASSEMBLED IN THE FIELD ACCORDING TO THE MANUFACTURER'S INSTRUCTIONS. WIRE MESH REINFORCEMENT AND/OR CLOSER POST SPACING MAY BE ORDERED BY THE ENGINEER IN AREAS WHERE HIGH RUNOFF VOLUMES ARE ANTICIPATED, OR LOW SPOTS WHERE SEDIMENT WILL BE COLLECTED.
2. PRIOR TO BEGINNING EARTHWORK OPERATIONS AT LOCATIONS DIRECTED BY THE ENGINEER, SILT FENCE SHALL BE CONSTRUCTED ALONG THE TOE OF PROPOSED EMBANKMENT AT THE LIMITS OF CLEARING.

[illegible]



EROSION CONTROL SPECIFICATIONS:

1. SOIL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IN ACCORDANCE WITH "NEW HAMPSHIRE STORMWATER MANUAL, VOLUME 3 – EROSION AND SEDIMENT CONTROL DURING CONSTRUCTION" 2008. THE CONTRACTOR SHALL HAVE REFERENCE TO THIS BOOK.
2. RECOGNIZING THAT IMMEDIATE ATTENTION TO EROSION CONTROL PRACTICES DRAMATICALLY IMPROVES SOIL AND MOISTURE CONSERVATION AND REDUCES NEGATIVE IMPACTS ON WATER QUALITY, THE CONTRACTOR SHALL GIVE HIGH PRIORITY TO THE DAILY AND TIMELY INSTALLATION OF BOTH TEMPORARY AND PERMANENT EROSION AND SEDIMENT CONTROL MEASURES. IMMEDIATE INSTALLATION OF PRACTICES USUALLY REDUCES LONG TERM COSTS TO THE CONTRACTOR AND PROVIDES BENEFITS TO THE DEVELOPER AND THE PUBLIC GOOD.
3. EROSION CONTROL PRACTICES ARE SHOWN ON THE PLANS WITH RESPECT TO LOCATION AS DETERMINED FROM EXISTING TOPOGRAPHY. CHANGES MAY BE INDICATED IN THE FIELD TO IMPROVE EROSION AND SEDIMENT CONTROL.
4. CONSTRUCTION SHALL PROCEED UNIT BY UNIT TO FACILITATE INSTALLATION OF EROSION CONTROL MEASURES AND THE COMPLETION OF GRADING, SEEDING, AND LANDSCAPING AS SOON AS POSSIBLE WITHIN A UNIT. THIS PROCEDURE SHOULD RESULT IN THE EXPOSURE OF THE SMALLEST PRACTICAL LAND AREA AT ANY ONE TIME.
5. AREAS ADJACENT TO STREAMS CALL FOR PARTICULAR ATTENTION WITH REGARD TO SILT INTERCEPTION. INSTALL SILT FENCES AS SHOWN ON PLAN AND IN DETAIL BEFORE EARTHWORK COMMENCES. ADDITIONAL FENCING MAY BE REQUIRED AS WORK CONTINUES.
6. ALL DISTURBED AREAS AND ALL PROPOSED GRASSED AREAS SHALL HAVE TOPSOIL SPREAD (4" MINIMUM) AND BE LIMED, FERTILIZED, TILLED, SEEDED AND MULCHED. ALL SLOPES 3:1 (1 RISE ON 3 RUN) AND STEEPER SHALL HAVE MULCH HELD IN PLACE WITH NETTING (OR OTHER APPROVED BIODEGRADABLE MATTING MATERIAL), STAPLED AND STAKED. EACH AREA SHALL BE LIMED, FERTILIZED, PREPARED, SEEDED AND MULCHED (WITH ANCHORED NETTING AS REQUIRED) WITHIN 3 DAYS OF FINAL GRADING OR TEMPORARILY STABILIZED WITHIN 21 DAYS OF INITIAL DISTURBANCE. WHEN PERMANENT SEEDING CANNOT BE INSTALLED BY SEPTEMBER 15, TEMPORARY SEEDING AND MULCHING OF ALL DISTURBED AREAS SHALL BE INSTALLED IMMEDIATELY AND MAINTAINED IN THAT CONDITION UNTIL PERMANENT PRACTICES CAN BE INSTALLED IN THE FOLLOWING PLANTING SEASON.
7. THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION, BUT IN NO CASE SHALL EXCEED 5 ACRES AT ANY TIME BEFORE DISTURBED AREAS ARE STABILIZED.
8. ALL AREAS SHALL BE STABILIZED WITHIN 45 DAYS OF INITIAL DISTURBANCE (SEE NOTE 10).
9. TEMPORARY STABILIZATION OF DISTURBED AREAS:

**SEEDBED PREPARATION:** TILL THREE INCHES DEEP MIXING IN FERTILIZER. APPLY LIME 2 TONS/ACRE (100#/1,000 SQ. FT.)  
**FERTILIZE:** UNIFORMLY APPLY NOT LESS THAN 300#/ACRE (7#/1,000 SQ. FT.) OF 10–20–20 OR EQUIVALENT.

**SEEDING:** SELECT APPROPRIATE SEEDING MIXTURE FROM TABLE 1 BELOW. SPREAD SEED UNIFORMLY. FIRM SOIL BY ROLLING OR PACKING; IF NOT FEASIBLE, THEN RAKE LIGHTLY TO COVER SEEDS.

**MULCHING:** MULCH ALL DISTURBED AREAS WITH 1–1/2 TO 2 TONS OF HAY OR STRAW PER ACRE (70–90#/1,000 SQ. FT.). ANCHOR ON ALL SLOPES 3:1 OR STEEPER AND FLATTER SLOPES SUBJECT TO WASH OR WIND BLOWN. USE JUTE (OR OTHER BIODEGRADABLE) NETTING. STAKING AND STAPLING MAY BE REQUIRED.

TABLE 1 – PLANT SELECTION AND SEEDING RATES			
SPECIES	PER ACRE	PER 1000 SQ.FT.	REMARKS
WINTER RYE	2 BU OR 112 LBS.	2.5 LBS.	BEST FOR FALL SEEDING. SEED AUGUST 15 TO SEPTEMBER 15 FOR BEST COVER. SEED TO DEPTH OF ONE INCH.
OATS	2 1/2 BU OR 80 LBS.	2 LBS.	BEST FOR SPRING SEEDINGS. LATER THAN MAY 15 FOR SUMMER PROTECTION. SEED TO DEPTH OF ONE INCH.
ANNUAL RYE	40 LBS.	1 LB.	GROWS QUICKLY. BUT IS OF SHORT GRASS DURATION USE WHERE APPEARANCES ARE IMPORTANT. COVER SEED WITH NO MORE THAN 1/4 INCH OF SOIL. WITH MULCH, SEEDING MAY BE DONE THROUGHOUT GROWING SEASON. OTHERWISE SEED EARLY SPRING OR BETWEEN AUGUST 15 & SEPTEMBER 15.

10. PERMANENT STABILIZATION OF DISTURBED AREAS:
- SEED BED PREPARATION: TOPSOIL (SANDY LOAM, LOAM, OR SILT LOAM), FRIABLE, FREE OF TREE ROOTS, WEEDS, STONES MORE THAN 1–1/2 INCHES IN DIAMETER OR LENGTH SHALL BE PLACED OVER ALL DISTURBED AREAS IN A 4" (MINIMUM) THICK LAYER.
- TOPSOIL: TOPSOIL SHALL BE FREE OF HERBICIDES AND TOXIC MATERIALS. TILL THREE INCHES DEEP MIXING IN THE FERTILIZER AND LIME. APPLY LIME AT RATES INDICATED IN TABLE "A".
- SEEDING: SELECT APPROPRIATE SEEDING MIXTURE FROM TABLE "C". SPREAD SEED UNIFORMLY. FIRM SOIL BY ROLLING OR PACKING; IF NOT FEASIBLE, THEN RAKE LIGHTLY TO COVER SEEDS.
- MULCHING: MULCH ALL DISTURBED AREAS WITH 1–1/2 TO 2 TONS OF HAY OR STRAW PER ACRE (70 – 90#/1,000 SQ. FT.). ANCHOR MULCH ON ALL SLOPES 3:1 OR STEEPER AND ON FLATTER SLOPES SUBJECT TO WASH (WATERWAYS AND/OR WINDBLOWN) USING BIODEGRADABLE NETTING (OR OTHER APPROVED BIODEGRADABLE MATTING MATERIAL), WITH STAKING AND STAPLING.

TABLE "A"–LIME APPLICATION RATES		
EXISTING SOIL pH	LIMESTONE TO BE ADDED	
	TONS/ACRE	POUNDS/CY
4.0–4.4	3	12
4.5–4.9	2	8
5.0–5.4	1	4
UNKNOWN	2	8

TABLE "C" – SEEDING GUIDE

USE	SOIL DRAINAGE				
	SEEDING MIXTURE 1/	DROUGHTY	WELL DRAINED	MODERATELY WELL DRAINED	POORLY DRAINED
STEEP CUTS AND FILLS, BORROW AND DISPOSAL AREAS	A	FAIR	GOOD	GOOD	FAIR
	B	POOR	GOOD	FAIR	FAIR
	C	POOR	GOOD	EXCELLENT	GOOD
	D	FAIR	FAIR	GOOD	EXCELLENT
	E	FAIR	EXCELLENT	EXCELLENT	POOR
WATERWAYS, EMERGENCY SPILLWAYS, AND OTHER CHANNEL WITH FLOWING WATER	A	GOOD	GOOD	GOOD	FAIR
	C	GOOD	EXCELLENT	EXCELLENT	FAIR
	D	GOOD	EXCELLENT	EXCELLENT	FAIR
LIGHTLY USED PARKING LOTS, ODD AREAS, UNUSABLE LANDS, AND LOW INTENSITY USE RECREATION SITES	A	GOOD	GOOD	GOOD	FAIR
	B	GOOD	GOOD	FAIR	POOR
	C	GOOD	EXCELLENT	EXCELLENT	FAIR
	D	FAIR	GOOD	GOOD	EXCELLENT
PLAY AREAS AND ATHLETIC FIELDS. (TOPSOIL IS ESSENTIAL FOR GOOD TURF.)	F	FAIR	EXCELLENT	EXCELLENT	2/
	G	FAIR	EXCELLENT	EXCELLENT	2/
GRAVEL PIT – SEE PM–NH–24 RECOMMENDATIONS REGARDING RECLAMATION OF SAND AND GRAVEL PITS. *					
1/ REFER TO SEEDING MIXTURES AND RATES IN TABLE "D".					
2/ POORLY DRAINED SOILS ARE NOT DESIRABLE FOR USE AS PLAYING AREAS AND ATHLETIC FIELDS.					
* SEE "VEGETATING NEW HAMPSHIRE SAND AND GRAVEL PITS: TECHNICAL NOTE PM–NH–24, UNITED STATES DEPARTMENT OF AGRICULTURE, SOIL CONSERVATION SERVICE, REVISION APRIL, 1991.					

11. TEMPORARY EROSION CONTROL MEASURES SHALL NOT BE REMOVED UNTIL ALL DISTURBED AREAS HAVE BEEN STABILIZED. AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED:  
A. BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED;  
B. A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED;  
C. A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH STONE OR RIPRAP HAS BEEN INSTALLED; OR  
D. EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.
- MAINTENANCE: DURING THE CONSTRUCTION PERIOD AND UNTIL SUCH TIME AS THE LONG TERM VEGETATION IS ESTABLISHED TO A 70% VEGETATIVE STAND.  
A. DISTURBED AREAS WILL BE FERTILIZED AND RESEEDED.  
B. CATCH BASINS WILL BE CHECKED AND CLEANED AS NECESSARY.  
C. DRAINAGE AND GRASS TREATMENT SWALES SHALL BE CHECKED FREQUENTLY AND CLEANED AS REQUIRED.  
D. THE SILT FENCES AND HAYABLE DIKES WILL BE CHECKED ON A REGULAR BASIS AND REPAIRED AS NECESSARY TO CORRECT ANY DAMAGE, DETERIORATION, AND SHORT–CIRCUITING.
12. REFER TO "EROSION AND SEDIMENT CONTROL PLAN" PRIOR TO ANY SITE DISTURBANCE. CONTACT ENGINEER FOR COPIES OF PLAN.
- INSPECTIONS: THE ENGINEER SHALL BE CONTACTED ON A REGULAR BASIS TO INSPECT ALL EROSION CONTROL PRACTICES AS WELL AS THE MAINTENANCE OF THE EROSION CONTROL COMPONENTS. REFER TO CONSTRUCTION SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS. EROSION CONTROL PRACTICES SHALL BE IN STRICT ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS.
13. ALL TREATMENT SWALES, DITCHES, AND LEVEL LIP SPREADERS SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.
14. FOR SPECIAL WINTER CONSTRUCTION CONSIDERATIONS, THE CONTRACTOR SHALL REFER TO THE "EROSION & SEDIMENT CONTROL PLAN".
15. THIS PROJECT SHALL BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF RSA 430.53 AND CHAPTER AGR 3800 RELATIVE TO SPECIES.

TABLE "D" – MIXTURES & RATES

MIXTURE	POUNDS PER ACRE	POUNDS PER 1,000 SQ. FT.
A. TALL FESCUE CREEPING RED FESCUE REDTOP TOTAL	20 20 2 42	0.45 0.45 0.05 0.95
	15 10 15	0.35 0.25 0.35
	40 or 30 or 55	0.95 or 0.75 or 1.35
	20 20 8 48	0.45 0.45 0.20 1.10
D. BIRDSFOOT TREFOIL REDTOP TOTAL	20 10 30	0.50 0.20 0.70
	20 20 50	0.45 0.45 1.20
	50 50 100	1.15 1.15 2.30
	150	3.60
1/ FOR HEAVY USE ATHLETIC FIELDS CONSULT THE UNIVERSITY OF NEW HAMPSHIRE COOPERATIVE EXTENSION TURF SPECIALIST FOR CURRENT VARIETIES AND SEEDING RATES.		

OTHER SEED MIXTURES AND SEEDING RATES AS RECOMMENDED BY THE USDA – NATURAL RESOURCES CONSERVATION SERVICE MAY BE USED WITH PRIOR WRITTEN PERMISSION FROM THE ENGINEER.

CONSTRUCTION SEQUENCE:

1. THE CONTRACTOR SHALL CONDUCT A PRE–CONSTRUCTION CONFERENCE WITH TOWN OFFICIALS PRIOR TO ANY WORK COMMENCING ON SITE.
2. FELL AND CLEAR TREES, AS REQUIRED. PLACE JOB TRAILER AT SPECIFIED LOCATION AND INSTALL CONSTRUCTION ENTRANCE(S). STABILIZE THE CONSTRUCTION ENTRANCE(S) WITH COARSE AGGREGATE 8 INCHES (MINIMUM) IN DEPTH, ON TOP OF A GEOTEXTILE, TO PREVENT OFF–SITE TRACKING BY VEHICLES AND EQUIPMENT.
3. INSTALL SILT FENCE AT ALL LOCATIONS INDICATED ON PLAN AND AT OTHER LOCATIONS AS DETERMINED BY THE ENGINEER. INSTALL OTHER TEMPORARY AND PERMANENT EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO EARTHWORK COMMENCING.
4. GRUB SITE AND DISPOSE OF DEBRIS, AS NECESSARY; CONTRACTOR TO LEGALLY DISPOSE OF DEBRIS OFF THE SITE.
5. STOCKPILE TOPSOIL AND INSTALL ASSOCIATED EROSION CONTROL MEASURES, I.E., SILT FENCE, AND MULCH.
6. PONDS AND SWALES SHALL BE INSTALLED EARLY ON IN THE CONSTRUCTION SEQUENCE (BEFORE ROUGH GRADING THE SITE) AND SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.
7. PLACE SELECT MATERIALS AND PAVEMENT FOR THE LIMITS OF THE PROPOSED ROADWAY IMPROVEMENTS. THE LIMITS OF THE ROADWAY IMPROVEMENTS SHALL BE STABILIZED WITHIN 72 HOURS AFTER GRADING.
8. INSPECT ALL DISTURBED AREAS ON A WEEKLY BASIS AND AFTER EVERY ONE–HALF INCH OF RAINFALL. FOLLOWING THESE INSPECTIONS, INSTALL ANY AND ALL TEMPORARY DRAINAGE, EROSION, AND SEDIMENT CONTROL PRACTICES AS INDICATED OR AS REQUIRED, I.E., DIVERSION CHANNELS, BERMS, DRAINS, DITCHES, SILT SACKS, SILT FENCES, SEED AND MULCH, OR ANY OTHER BEST MANAGEMENT PRACTICES AS RECOMMENDED AND SPECIFIED IN THE "STORMWATER MANAGEMENT AND EROSION AND SEDIMENT CONTROL HANDBOOK FOR URBAN AND DEVELOPING AREAS OF NEW HAMPSHIRE" (USDA – SOIL CONSERVATION SERVICE).
9. PLACE TOPSOIL, COMPLETE PERMANENT FERTILIZING, LIMING, SEEDING AND MULCHING, AND INSTALL LANDSCAPE PLANTING.
10. CLEAN AND RESTORE SILT DESTINATION SITES. REMOVE OTHER EROSION CONTROL PRACTICES ON A TIMELY BASIS AS PERMANENT MEASURES TAKE HOLD. SPOT FERTILIZE, SEED, AND MULCH AS REQUIRED. NO RUNOFF SHALL BE DIRECTED TO THE PERMANENT MEASURES UNTIL THEY ARE ESTABLISHED.
11. INSPECT AND MAINTAIN GRADING, EROSION CONTROL AND SEDIMENT CONTROL PRACTICES WEEKLY AND INSPECTION SHOULD OCCUR AFTER EVERY 0.5" OR GREATER RAINFALL WITHIN A 24 HOUR PERIOD.
12. REFER TO "EROSION AND SEDIMENT CONTROL PLAN" FOR ADDITIONAL DETAILS RELATIVE TO THE REQUIRED CONSTRUCTION SEQUENCE. MAINTENANCE OF ALL EROSION CONTROL COMPONENTS SHALL BE AN ONGOING PRACTICE AND IN STRICT ACCORDANCE WITH THE APPROVED PLAN.

SPECIAL WINTER CONSIDERATIONS

THE MAJOR FOCUS OF WINTER EROSION AND SEDIMENT CONTROL IS THE PERIODS OF INTENSE RUNOFF ASSOCIATED WITH MID–WINTER THAWS AND RAINSTORMS, AND THE SPRING MELT.

FROZEN GROUND MAKES THE INSTALLATION AND MAINTENANCE OF EROSION CONTROL MEASURES VERY DIFFICULT. INSTALLATION SHOULD TAKE PLACE WELL BEFORE THE GROUND FREEZES. MAINTENANCE IN WINTER WILL BE MUCH MORE TIME CONSUMING AND DIFFICULT THAN IN THE SUMMER. THE OVERALL CONSTRUCTION SCHEDULE AND THE WEEKLY WORK SCHEDULE WILL BE DEVELOPED TO INCREASE TIME, EFFORT, AND MANPOWER DEVOTED TO MAINTAINING THE EROSION AND SEDIMENT CONTROL MEASURES.

INTENSE RUNOFF IN MID–WINTER THAWS AND RAINSTORMS, AND THE SPRING MELT PERIOD, CAN RESULT IN MORE SEVERE EROSION AND SEDIMENTATION PROBLEMS THAN RUNOFF FROM SUMMER STORMS. THE SOIL IS OFTEN COMPLETELY SATURATED WITH WATER, AND IS ALSO OFTEN UNDERLAIN BY A FROST LAYER. BOTH OF THESE FACTORS RESULT IN A GREATER PERCENTAGE OF THE RAIN OR MELTWATER RUNNING OVER THE GROUND SURFACE. WINTER AND SPRING RAINSTORMS ARE OFTEN HEAVIER AND MORE INTENSE THAN SUMMER SHOWERS. FOR THESE REASONS, EROSION AND SEDIMENTATION CAN BE ESPECIALLY SEVERE IN MID–WINTER THAWS AND THE SPRING MELT.

1. CONTROL MEASURES FOR WINTER CONSTRUCTION:

- A. ALL PROPOSED VEGETATED AREAS WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING, ELSEWHERE. THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS;
- B. ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED TEMPORARILY WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS; AND
- C. AFTER NOVEMBER 15TH, INCOMPLETE ROAD OR PARKING SURFACES, WHERE WORK HAS STOPPED FOR THE WINTER SEASON, SHALL BE PROTECTED WITH A MINIMUM OF 3 INCHES OF GRAVEL PER NHDOT ITEM 304.2.
- D. MINIMIZE DISTURBED AREA AND TIME OF DISTURBANCE: DISTURBED AREA AND LENGTH OF DISTURBANCE SHALL BE MINIMIZED ESPECIALLY BETWEEN OCTOBER 15TH AND MAY 1ST.
- E. GRASSED OR RIP RAPPED SWALES AND DITCHES: INSTALLATION WILL OCCUR BEFORE GROUND FREEZES. CHANNELS ARE TO BE STABILIZED WITH STONE, RIPRAP, OR VEGETATION IMMEDIATELY. INSPECTIONS ARE TO BE FREQUENT WITH REMOVAL OF ANY FLOW BLOCKAGE CAUSED BY ICE OR SEDIMENT.
- F. MULCHING: MULCH ALONE SHOULD NOT BE CONSIDERED AN ADEQUATE EROSION AND SEDIMENT CONTROL TECHNIQUE FOR AREAS THAT ARE DISTURBED IN THE WINTER OR SPRING. MULCH IS EASILY WASHED AWAY BY INTENSE RUNOFF FLOWING OVER SATURATED OR FROZEN SOIL. IT IS ESSENTIAL THAT MULCH BE LAID DOWN IN SUCH A WAY THAT IT WILL NOT BLOW OR WASH AWAY.
- G. SILT FENCE: INSTALLATION IS REQUIRED BEFORE THE GROUND FREEZES, OTHERWISE STAKES WILL BE DIFFICULT TO DRIVE. INSPECT FREQUENTLY AND REMOVE ANY COLLECTED SEDIMENT IN ORDER TO PROVIDE AS MUCH CAPACITY AS POSSIBLE.
- H. SNOW FENCE: INSTALLATION IS REQUIRED BEFORE THE GROUND FREEZES OTHERWISE STAKES WILL BE DIFFICULT TO DRIVE. FENCES MUST BE PLACED LIBERALLY AROUND THE WORK SITE TO KEEP SOIL DISTURBANCE TO AN ABSOLUTE MINIMUM.
1. STONE CHECK DAMS: PER DETAIL THE PLACEMENT WILL OCCUR IN SWALES AND DITCHES AFTER FINAL GRADING AND IS TO BE MAINTAINED UNTIL THE SITE IS FULLY STABILIZED.
2. INSPECTION AND MAINTENANCE
- INSPECTION OF EROSION AND SEDIMENT CONTROL MEASURES IS REQUIRED MORE FREQUENTLY IN THE WINTER AND SPRING THAN IN THE SUMMER. CAREFUL ATTENTION MUST BE GIVEN TO WEATHER PREDICTIONS. INSPECTION OF ALL CONTROL MEASURES WILL BE ONGOING TO ENSURE THAT STRUCTURES WILL MANAGE THE POTENTIALLY HEAVY AND INTENSE RUNOFF. CONSTANT MAINTENANCE OF CRITICAL CONTROL MEASURES MAY BE NECESSARY DURING THE WINTER AND EARLY SPRING TO PREVENT FAILURE OR OVERLOADING OF CONTROL MEASURES. A SECOND LINE OF CONTROL WILL BE QUICKLY INSTALLED IF PROBLEMS OCCUR. A SUBSTANTIAL AMOUNT OF TIME, EQUIPMENT, AND MANPOWER SHALL BE DEVOTED TO EROSION AND SEDIMENT CONTROL.
3. FOLLOW–UP
- INSTALLATION OF PERMANENT VEGETATIVE CONTROLS WILL BE REQUIRED AS EARLY AS IS PRACTICAL AT THE BEGINNING OF THE GROWING SEASON.

EROSION CONTROL NOTES

PREPARED FOR:  
TOWN OF BEDFORD  
55 CONSTITUTION DRIVE  
BEDFORD, NEW HAMPSHIRE 03110

POLLY PEABODY ROAD RECONSTRUCTION PLANS

BEDFORD, NEW HAMPSHIRE

SHEET: 11 OF 21

DATE: APRIL 6, 2022










SCALE: AS SHOWN

NO.

DATE

REVISION DESCRIPTION





POLLY PEABODY ROAD  
CROSS SECTIONS  
100+50 TO 104+00

PREPARED FOR:  
**TOWN OF BEDFORD**  
55 CONSTITUTION DRIVE  
BEDFORD, NEW HAMPSHIRE 03110











POLLY PEABODY ROAD  
RECONSTRUCTION PLANS










BEDFORD, NEW HAMPSHIRE

SHEET: 12 OF 21	SCALE: AS SHOWN
-----------------	-----------------










DATE: APRIL 6, 2022

NO.	DATE	REVISION DESCRIPTION
-----	------	----------------------

[illegible]



<p>POLLY PEABODY ROAD RECONSTRUCTION PLANS</p> <p>BEDFORD, NEW HAMPSHIRE</p>	<p>PREPARED FOR:</p> <p>TOWN OF BEDFORD 55 CONSTITUTION DRIVE BEDFORD, NEW HAMPSHIRE 03110</p>	<p>POLLY PEABODY ROAD CROSS SECTIONS 108+00 TO 110+04</p>
<p>14 OF 21</p> <p>SCALE: AS SHOWN</p>	<p>DATE: APRIL 6, 2022</p>	



V: 1"=10'

POLLY PEABODY ROAD  
CROSS SECTIONS  
110+50 TO 113+00

PREPARED FOR:  
**TOWN OF BEDFORD**  
55 CONSTITUTION DRIVE  
BEDFORD, NEW HAMPSHIRE 03110

# POLLY PEABODY ROAD RECONSTRUCTION PLANS

BEDFORD, NEW HAMPSHIRE


SHEET: 15 OF 21	SCALE: AS SHOWN
-----------------	-----------------

DATE: APRIL 6, 2022


DATE: APRIL 6, 2022	
---------------------	--

NO.	DATE	REVISION DESCRIPTION
-----	------	----------------------







114+20




114+00




113+50




113+05




115+50




115+00












114+50












114+35



POLLY PEABODY ROAD RECONSTRUCTION PLANS		TOWN OF BEDFORD 55 CONSTITUTION DRIVE BEDFORD, NEW HAMPSHIRE 03110		POLLY PEABODY ROAD CROSS SECTIONS 113+05 TO 115+50		NO.		DATE		REVISION DESCRIPTION	
SHEET: 16		OF 21		SCALE: AS SHOWN		DATE: APRIL 6, 2022					



POLLY PEABODY ROAD RECONSTRUCTION PLANS		PREPARED FOR: TOWN OF BEDFORD 55 CONSTITUTION DRIVE BEDFORD, NEW HAMPSHIRE 03110		POLLY PEABODY ROAD CROSS SECTIONS 116+00 TO 118+60		NO.		DATE		REVISION DESCRIPTION	
SHEET: 17		OF 21		SCALE: AS SHOWN							



POLLY PEABODY ROAD  
CROSS SECTIONS  
119+00 TO 121+50

PREPARED FOR:  
**TOWN OF BEDFORD**  
55 CONSTITUTION DRIVE  
BEDFORD, NEW HAMPSHIRE 03110










POLLY PEABODY ROAD  
RECONSTRUCTION PLANS

SHEET: 18 OF 21	SCALE: AS SHOWN
-----------------	-----------------

DATE: APRIL 6, 2022

DATE: APRIL 6, 2022	
---------------------	--

NO.	DATE	REVISION DESCRIPTION
-----	------	----------------------



POLLY PEABODY ROAD  
CROSS SECTIONS  
121+92 TO 124+50

PREPARED FOR:  
**TOWN OF BEDFORD**  
55 CONSTITUTION DRIVE  
BEDFORD, NEW HAMPSHIRE 03110

POLLY PEABODY ROAD  
RECONSTRUCTION PLANS

BEDFORD, NEW HAMPSHIRE

SHEET: 19	OF 21	SCALE: AS SHOWN
-----------	-------	-----------------


DATE: APRIL 6, 2022

NO.	DATE
-----	------


DATE \_\_\_\_\_

REVISION	DESCRIPTION
----------	-------------







126+50




126+00




125+50




125+00




128+00




127+50



127+00



126+85



POLLY PEABODY ROAD  
CROSS SECTIONS  
125+00 TO 128+00

PREPARED FOR:  
TOWN OF BEDFORD  
55 CONSTITUTION DRIVE  
BEDFORD, NEW HAMPSHIRE 03110

POLLY PEABODY ROAD  
RECONSTRUCTION PLANS  
BEDFORD, NEW HAMPSHIRE

SHEET: 20 OF 21






DATE: APRIL 6, 2022

SCALE: AS SHOWN

REVISION DESCRIPTION

DATE

NO.



<p>POLLY PEABODY ROAD RECONSTRUCTION PLANS</p> <p>BEDFORD, NEW HAMPSHIRE</p>			<p>PREPARED FOR:</p> <p>TOWN OF BEDFORD 55 CONSTITUTION DRIVE BEDFORD, NEW HAMPSHIRE 03110</p>		<p>POLLY PEABODY ROAD CROSS SECTIONS 128+50 TO 129+50</p>			
<p>SHEET: 21 OF 21</p> <p>SCALE: AS SHOWN</p>			<p>DATE: APRIL 6, 2022</p>				<p>NO.</p> <p>DATE</p> <p>REVISION DESCRIPTION</p>	